



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

AFF.NO:-3430004
School No:-66230
Ph:-2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची ८३४००२

No. JVM/OT-05 /2021-22

Date: 06-09-2021

INVITATION TO RE-TENDER

Principal, JVM invites tender for the subject given below. Salient feature are given in the table and detail of scope of work and tender conditions are given in "invitation to re-tender " dated 06-09-2021 enclosed herewith. (Total pages -9) which earlier tender floated on 23-08-2021.

Subject: Re-Tender for Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.JVM premises.

Salient Features of the Invitation to Tender

1	Tender Enquiry No. & Date	No. JVM/OT-05/2021-22 Date: 06-09-2021
2	Project Description	Re-Tender for Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work. JVM premises.
3	Pre Bid Meeting	11.09.2021 at 1.00 PM
4	Last date & time of submission of tender document	13.09.2021 by 01.00 PM
5	Date & Time of Opening of Re-Tender	On 13-09-2021 at 5.00 PM. The representatives from the tenderer may be present while opening of the tender.
6	Validity of tender	03 (Three) months from the due date of opening of Techno-Commercial part of the tender document.
7	Completion Time	One month from the date of issue of work order.
8	Earnest Money Deposit	Rs. 12000/- (Twelve thousand only)
9	Cost of the tender document	Rs. 1000/- (One thousand) only

(SAMARJIT JANA)

• PRINCIPAL

Principal
Jawahar Vidya Mandir
Shyamali, Ranchi - 2

Diagh



Dated: 06.09.2021

INVITATION TO RE-TENDER

Subject: Re-Tender for Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.JVM premises

Sealed tenders are invited for award of **Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.JVM premises**, Ranchi as per the Technical Specification attached as Annexure – I from registered, reputed, experienced and eligible firms who have executed similar nature of work in Schools/ Institutions/Organizations and satisfying all the terms and conditions in this tender document.

1.0 Instructions to Tenderer

- 1.1 Tenderer are advised to go through the entire documents completely before quoting for the tender.
- 1.2 Tenders are invited in two bid system (i) Techno-commercial Bid & (ii) Price Bid. The 'Techno-commercial Bid' will be made and put in the first envelope containing the title '**Techno-commercial Bid**'. It should contain full information as required in Techno Commercial Bid Declaration by the Bidder. The 'Price Bid' will be made and put in the second envelope containing the title '**Price Bid**'. It could include full information as required in Annexure. Both bids should be put in the third envelope which should be prominently super-scribed as "**Re-Tender for Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.JVM premises Ranchi.**" and addressed to "The Principal, Jawahar Vidya Mandir, Shyamali colony, Ranchi – 834002" on or before **13.09.2021** till **1.00 PM**. The tenders will be opened on date at **5.00 PM** on **13.09.2020**.
- 1.4 Tenders received after due date and time mentioned above, as well as those received without separate sealed envelopes as specified above will not be accepted.
- 1.5 It may be noted that incomplete in any respect or conditional tender will not be accepted.

2.0 Eligibility Criteria

A- TECHNICAL:

- 2.1 Work order and completion /Execution certificate for civil work related to any residential / commercial / institutional/ Industrial project completed during last 7 (seven) years on last day of preceding month in which this tender is floated.

B-COMMERCIAL:

- 2.2 Bidder must be registered in PF and ESIC, and also to submit proof of remittance proceedings last financial year.
- 2.3 The Bidder should have the GST and PAN (*Copies of GST Regn. and PAN*).
- 2.4 The bidder shall submit self attested copy of all necessary documents in support of above clause no. 2.1 , 2.2 , & 2.3

3.0 Earnest Money Deposit: All the tenderers shall be accompanied by EMD (Earnest money deposit) of Rs. 12,000/- (Rupees twelve thousands only) payable to "Jawahar Vidya Mandir, Shyamali Ranchi " in the form of" demand draft" or at par cheque. Tenders received without EMD are liable to be rejected.EMD shall be refunded to

Sam
06/09/21
ra

High



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

AFF.NO.-3430004
School No.: 66230
Ph.: 2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची 834002

successful bidder after execution of order and to unsuccessful bidder after finalization of work order.

- 4.0 Cost of the Tender :** The cost of the tender will be Rs.1000/- (One thousand only) non-refundable in the form of a Demand draft/ At PAR CHEQUE drawn on any Nationalized/ Schedule Bank in favour of Jawahar Vidya Mandir.

IF A FIRM FILING TENDER DOES NOT FULFILS ALL OR ANY OF THE ABOVE ELIGIBILITY CRITERIA MENTIONED ABOVE, THE TENDER OF THE FIRM WILL NOT BE CONSIDERED.

5.0 SCOPE OF WORK:

Sl. No.	Description	Make /Model No.	Quantity
1.	Tender for Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.JVM premises Ranchi		a/s indicated in BOQ

- 6.0 PRICE:** The Tenderer shall quote for the items indicated above on for JVM, Shyamali, Ranchi basis. The quoted price shall be firm and binding and shall not be subject to any variation whatsoever on any account till completion of supply. All applicable taxes & duties shall be indicated separately. **(Un-priced copy of Price Bid indicating "quoted" against each item should be submitted along with Techno-commercial bid).**

- 7.0 TAXES & DUTIES:** Except as otherwise specifically provided in the order, the Tenderer shall bear and pay all taxes, duties, levies as charges for the subject work.

- 8.0 VALIDITY OF RATES:** The rate quoted by the Tenderer shall remain valid for a period of 6 (six) months from the date of opening of quotation.

9.0 TIME SCHEDULE:

- 9.1** The successful Tenderer shall be required to complete the job within one month from the date of receipt of order.

- 9.2** In the event the supplied material is not conforming to the ordering specification and approved make/brand, the material so supplied will be rejected without paying any price/ compensation. The decision of JVM in this regard will be final.

10.0 PAYMENT TERMS:

The payment shall be released after completion of work against submission of bill with measurement basis duly certified by supervisor / Engineer incharge of JVM Shyamali.

5% of bill value shall be deducted from the bill and refund after completion of warrantee period /maintenance/ guarantee period (6 months)

Other taxes and duties shall be applicable as per statute. GST reg. no. shall be mentioned in all tax invoices

Handwritten signature and date: 06/09/21

Handwritten initials: sd

Handwritten signature



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

AFF.NO.-3430004
School No.:66230
Ph.:2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची ८३४००२

The contractor is requested to confirm acceptance of all terms and conditions as mentioned above.

- 11.0 INSPECTION:** The inspection of materials shall be carried out by JVM after receipt of materials at destination.
- 12.0 LIQUIDATED DAMAGES:** Time and date stipulated in the Contract for completion of delivery shall be deemed to be the important activity of the Contract. If, however, the Tenderer fails to fulfill the completion within the time schedule, or within such extended time schedule as may be further granted, the Tenderer shall be liable to pay as Liquidated Damages (LD) and by way of penalty a sum of 0.5% of the contract price per week of delay or part thereof, and such liquidated damages shall be limited to a maximum ceiling of 5% of the Contract Price
- 13.0 ACCEPTANCE OF ORDER:** JVM is not bound to accept lowest or any Tender or to assign reasons whatsoever for non-acceptance. JVM also reserves the right to cancel the tender without assigning any reason whatsoever.
- 14.0 EVALUATION OF TENDER:** Tenderer should quote for all the items as per enclosed price bid format (Annexure-I). Part offer or incomplete offer shall be liable to be rejected. Price of the techno-commercially eligible tenderer shall be evaluated on overall basis.
- 15.0 NO CLAIM OR COMPENSATION FOR SUBMISSION OF TENDER:** The Tenderer whose Tender is not accepted shall not be entitled to claim any costs, charges, expenses of and incidental to or incurred by him through or in connection with his submission of Tender, even though JVM may elect to withdraw the Invitation of Tender
- 16.0 NEGLIGENCE, DEFAULT AND RISK PURCHASE**
- 16.1** If the Tenderer fails to execute the work with due diligence or expedition or shall refuse or neglect to comply with any order given to him in writing by JVM in Contract, JVM may give notice in writing to the Tenderer calling upon him to make good the failure, neglect or contravention within such time as may be deemed reasonable and in default of the compliance with the said notice, JVM without prejudice to its rights under the Contract, may rescind or cancel the Contract holding the Tenderer liable for the damages that JVM may sustain in this regard.
- 17.1** JVM may at any time temporarily stop the work under the Contract or any part thereof by serving notice in writing to the Tenderer. Work so suspended shall be resumed by the Tenderer on receipt of instructions from JVM in writing. JVM will not be liable to the Tenderer for any damage or loss caused by such period of suspension of work.
- 17.2** JVM will be at liberty to terminate the Contract without prejudicing its right and affecting the obligations of the Tenderer by giving 15 days' notice in writing in the following events:
- a) If the Tenderer fails to comply with the provision/provisions of the Contract.
- b) If the Tenderer is involved in any action involving moral turpitude.

The tenderers are requested to confirm acceptance of all terms & conditions as per tender enquiry.

(SAMARJIT JANA)
PRINCIPAL

[Signature]



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

AFF.NO:-3430004
School No.:-66230
Ph:-2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची ८३४००२

Annexure-1

Sub : Roof structure with sheet cover for open space of first floor of Golden jubilee block and associated civil work.

sl.	DSR	Description	Unit	Qty	Rate	Amount
1		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	Cum	3.0		
2		Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	7.0		
3		Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	7.0		
4		Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	84.0		
5		Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping or concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately) All works above plinth level upto floor V level cum 9400.85	Cum	1.0		
6		Bricks work in CM (1:6) in superstructure with approved quality of clean course sand of FM 2 to 2.5 (brick shall be free issue item)	cum	12.0		
7		15 mm cement plaster on rough side of single or half brick wall of mix : 1:6 (1 cement: 6 coarse sand) including scaffolding	Sqm	73.0		
8		12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand) sqm 263.55	Sqm	58.0		
9		Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. complete 11.46.2 Size of Tile 600x600 mm	Sqm	55.0		
10		Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	850.0		
11		Fixing colour coated welded profile sheeting using self tapping screw of size 5.5 x 5.5 mm with EPDM seal. Only sheet shall be free issue items. All other fixtures supply like screw clamp etc shall be in bidder's scope	Sqm	57.0		
12		Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. sqm 115.15	Sqm	114.0		
13		Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	114.0		
14		Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	77.0		
15		Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	31.0		
16		Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanizing @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross 'T' of size 24x28 mm made out of 0.33 mm	Sqm	56.0		



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

AFF.NO.-3430004
School No.:66230
Ph.:2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची ८३४००२

	centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required, Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyester baked paint, for all eights, as per specifications, drawings and as directed by Engineer-in-Charge				
17	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double fibre panes, and silicon sealant shall be paid separately) Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Two track two panels sliding window made of (Big series) frame 67 x 50 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of window above 1.75 sqm upto 2.50 sqm) with 5mm fibre glass.	Sqm	9.0		
	TOTAL				

Heigh

Sanj

sd



General Condition of Contract (G.C.C.)

1. Your scope of work shall include all workers, suppliers and services for completion of entire work as directed through site order.
2. The contractor shall have own site office, stores, godown as may required for carrying out the subject work.
3. Provision of all labours, skilled, semi skilled, as may be required to complete the work.
4. Providing adequate tools, instruments, tackles, scaffolding etc. for completion of entire work.
5. Procurement of all the materials, as may be required for carrying out the work.
Abide by statutory regulations, labours rules, safety codes during execution of work.
6. Abiding by all statutory obligations including ESI, EPF etc . during execution of work and shall submit all evidence in this respect such as ESI, EPF certificates and minimum wage certificate along with each and every bill.
7. Contractor shall make arrangement at his own cost for drawing and distributing water and power from single point each where water and power will be provided by JVM free of cost.
8. Undertaking all works including repairs and renovation work for completion to the satisfaction of JVM.
9. Agency and/or the worker engaged by agency will not have any claim for payment employment in JVM. The age limit of worker shall be between 19 yrs. and 60 yrs.
10. Rate of wage shall not be less than the minimum wages plus prevailing percentage of EPF, FP, ESI, EDLI, Bonus etc. as required under the law.
11. Agency shall ensure fulfillment of al labour regulations/rules under the Labour Act and all other statutory requirement of Government of India and Government of Jharkhand.
12. Monthly bill based on actual deployment of worker shall be submitted by Agency statutory payment) viz. EPF, FP, ESI, EDLI, bonus etc.) including taxes payable if any.
13. Unit rates of all the items shall remain firm, fixed and binding on the contractor during entire period of execution of work and shall not be subjected to, any variation whatsoever on any account.
14. This being a unit rate contract, the payment shall however be released against actual quotations of work however be released against actual quantities of work executed duly certified by the JVM.
15. Unless other wise specified, measurement of work shall be carried out at site jointly by JVM & Contractor.
16. **Liquidated damages for non-fulfillment of completion schedule.** If the completion of work is delayed beyond the scheduled date for any reason other than due to force major condition or for those attributable to the contractor, then the contractor shall pay 1% per month of delay on total value of work up to a maximum of 5% of the final contract price.
17. The contractor shall not sublet/sub contract the whole or any part of work failing which the contract may be terminated.
18. No completion certificate shall be issued or shall be work be considered to be complete until the contractor removes from the site all scaffolding, surplus materials, rubbish etc.
19. **Maintenance Guarantee Period (defect liability period):** The contractor guarantees that for a period of 12 (twelve) months commencing from the date of completion of contract. He shall undertake reconstruction rectification, replacement of all regular schedule work and any other work to make good the faulty work as stated under completion certificate for period of 06 (six) months from the date of issue of commissioning certificate.

Signature

Signature

Signature



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI - 834002

AFF. NO. - 3430004
School No. - 66230
Ph. - 2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची 834002

20. The contractor shall have a valid labour license and shall also maintain all records/ register/return/cards under state contract labour (R&A) rules act such as :-
- i) Register of workmen employed by contractor : Form - 9
 - ii) Employment card : Form - 10
 - iii) Muster roll : Form - 12
 - iv) Register of wages-cum-muster roll : Form - 13
 - v) Wage slip : Form - 15
 - vi) Register of over time : Form - 19
 - iii) Submission of Return in Form - 20
21. All materials supplied to the site shall be of good quality as per latest revision of CPWD specification. Any material not approved by the Engineer shall be removed from the site at his own cost by the Contractor.
22. Brick and Colour coated sheet is free issue item.
23. The work carried at site as per latest edition of CPWD specification.
- ~~24.~~ Further, JVM also reserves the right to cancel the tender without assigning any reasons for the same. In such event JVM shall return the Earnest money deposit.

Sam

sd

Devg



JAWAHAR VIDYA MANDIR

SHYAMALI, RANCHI – 834002

AFF.NO.-3430004
School No.-66230
Ph.:2411221, 2411665

जवाहर विद्या मंदिर, श्यामली, राँची ८३४००२

Special condition of contract (S.C.C.)

Work : Aluminum work for Partition, doors, Providing and Fixing false ceiling, flooring, painting and electrical fitting and construction work, Jawahar Vidya Mandir, Shyamali, Ranchi -2

1. The contractor may be asked to carry out the above mentioned work. The contractor is to execute the work as per existing UPVC window. The changes in quantity may increase or decrease as given in BOQ. and contractor should do the work as per direction/ requirement of site engineer/supervisor.
2. The work will be executed on firm item rates basis as quoted. The contractor will be issued with site order indicating various works to be taken up by the contractor.
3. Any defect found within the guarantee period shall have to be attended by the contractor at their own cost and risk.
4. The institutional building regulations of the safety code shall have to be strictly followed by the contractors.
5. The work is to be executed as per specifications mentioned in BOQ and direction of site engineer. **The quantity mention in BOQ is tentative, it may increase or decrease. The payment will be on actual measurement and consumption of items.**
6. Terms of payment : Contractor shall submit Bill in triplicate alongwith measurement sheet/abstract of the quantity being executed by the contractor at site, Income Tax Registration no. (PAN) and Service tax registration no.
8. Work measurement sheet should be on printed form/letter head of the contractor duly signed and stamped by the contractor and certified by JVM site engineer.
9. T.D.S. will be affected from all payments as per prevailing rules.
10. 5 % (five percent) work value shall be paid after completion of warranty period/ maintenance guarantee period (6 months)and submission of pre-receipted invoice and completion of all his contractual certified by JVM along with submission of following documents :-
 - a) Completion certificate issued by JVM – original,
 - b) No dues certificate from JVM
 - c) No claim/no demand certificate by the contractor – original
 - d) Copies of all statutory documents to be provided by the contractor as required by JVM
11. JVM shall deduct taxes at source as per prevailing status from the payment to be made to the contractor. JVM shall deposit amount thus deducted with the concerned authorities and issue necessary certificates to the contractor to this effect.

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]